

NAKURU TOWN SECTION ONE: RAILWAYS TO MOGAS

BILL OF QUANTITIES						15/05/2019
MEDIAN 1						
ITEMS	DESCRIPTION	height	QTY	UNIT	RATE KSHS	TOTAL AMOUNT
3	Spathodea nilotica	4 ft.	300	pcs		
4	Australian flame	4 ft.	300	pcs		
5	Red bottle brush	4 ft.	15	pcs		
	Sub- total					
1	Red soil		20	tonnes		
2	manure		2	tonnes		
	Add 16% VAT					
	Sub- total					
Total						
MEDIAN 2						
2	Bougainvillea		224	pcs		
	Sub-total					
1	Red soil		30	tonnes		
2	manure		5	tonnes		
	Add 16% VAT					
3	County message board on two lamp poles		2	pcs		
	Sub-Total					
Total						
MATERIALS FOR ROUND TUBE STANDS(10ft tall 1ft underground and 2ft x2ft cross at the top and 1ftx 1ft bottom cross to anchor into the concrete) FOR DOUBLE BOUNGAINVILLEA SHRUBS						
	ITEM		QUANTITY	UNIT	RATE	AMOUNT
1	Metal stand (galvanized iron 3/4inch, 14G).		224	pcs		
2	Concrete(1:2:4)		5	M3		
	sub-total					
TOTAL						
Ground Levelling(the stretch opposite state house (from mazerous shop to Delux hotel)						
	un even ground levelling and use of top soil		200	tonnes		
	Levelling and Compaction					
Ground Levelling from delux to sec 58						
	un even ground levelling and use of top soil		250	tonnes		
	Levelling and Compaction					

	Labour	10 *5(days	persons		
	Maintenance (4 months)	10	Persons		
	Watering for 3 months (Twice a week)	120,000 litres per week	Trucks load 15,000 lts		
	Sub total				
	Grand total (KSH)				