

MINISTRY OF AGRICULTURE, LIVESTOCK AND FISHERIES
KIHINGO DRAINAGE CHANNEL-BILL OF QUANTITIES (PHASE 2)

SNo.	ITEM DESCRIPTION	UNITS	QUANTITIES	RATE (KShs)	AMOUNT (KShs)
1	Allow a prime cost for mobilization and demobilization of machinery and staff.	PC sum	100,000		
2	Bush clearing along the Cut-off-drain by removal of hedges, bushes, vegetation and other deleterious materials as directed by the Engineer.	M ²	1,000		
3	Excavate/desilt, grade in hard material to shape the cut-off-drain to free flow conditions including cart to spoil any excess vegetation, debris and soil as and where directed by the Engineer.	M ³	4,000		
4	Fabricate and erect project name board in 50mm diameter 3mm thick steel pipes as per attached drawing	1	NO		20,000
5	Allow a sum of Kenya Shillings Ten Thousand only for PIMC		SUM		10,000
6	Allow a prime cost for attendance to the Engineer's and supervisor's (project management)	PC sum	70,000	1	70,000
	TOTAL				
	GRAND TOTAL				